

CH-25 & Ch-29
Construction Safety
Homework Answers



01

Which of the following types of welding produces ozone?

A. Gas Metal Arc Welding

B. Sweating Carbon Rod

C. Brazing

D. Oxyacetylene welding



02

Airborne zinc oxide resulting from welding galvanized iron would be classified as:

A. Dust

B. Smoke

C. Fume

D. Mist



03

The two main types of tubular scaffolds are:

- A. **Tube type and frame type**
- B. Frame type and hanging type
- C. Hanging type and truss type
- D. Jointed and non-jointed



04

Shoring is required for all trenches more than 4 feet deep unless:

A. They are sloped to the angle of repose.

B. The trench is in stable rock

C. A ladder is provided

D. Only (a) and (b) above



05

OSHA regulations require adequate bracing and shoring or a sloped trench when the depth of excavation is more than:

- A. 3 ft
- B. 5 ft
- C. 10 ft
- D. 4 ft



06

The guard on a grinding wheel must:

- A. Completely enclose the wheel.
- B. Cover the wheel as completely as the nature of the work permits
- C. Be adjustable
- D. Only (b) and (c) above**



07

To what percentage of the rated load must a crane be tested?

A. 75%

B. 100%

C. 125%

D. 150%



08

The boom indicator on a mobile crane:

- A. Provides the angle of the boom
- B. Shows the safe load with the boom at any angle**
- C. Indicates load capacity
- D. Signals when the crane is out of balance



09

For the purpose of protecting workers in trenches, the type of soil is required to assess risk. A primary factor in differing types of soil is:

- A. Depth
- B. **Cohesiveness**
- C. Width
- D. Soil weight



10

The proper angle to place a ladder to ensure adequate safety is:

A. 4:1

B. 16:2

C. 4:4

D. 16:8



11

Which situation could lead to increased hazards associated with an open excavation?

- A. Heavy machinery is in operation near the excavation site.**
- B. The excavation is being conducted by an employee with less than 1 year of experience.
- C. The soil type of the excavation is A and C.
- D. Several excavations are situated on the same job site.



12

A safety monitor system for roofers is what method in the hierarchy of fall protection?

- A. Fall Arrest Systems
- B. Elimination of Fall Hazards
- C. Personal Protective Equipment (PPE)
- D. **Administrative Controls**



13

Personal fall arrest systems (PFAS), when stopping a fall, shall be rigged such that:

- A. The PFAS has a maximum arresting force of 5000 pounds or five times the potential impact energy of an employee
- B. An employee cannot free fall more than 6 feet or contact any lower level**
- C. The PFAS has a separate anchorage point for each employee
- D. An employee can use a self-retracting lanyard or lifeline



14

You have an oxygen cylinder and an acetylene cylinder stored within 1 foot of each other. Which would be the most appropriate solution to this hazard?
Note: the cylinders were not stored on a cart.

- A. Separate the cylinders by a minimum of 10 feet
- B. Place the acetylene cylinder in an explosion-proof room
- C. Separate cylinders by a 5-foot, ½-hour fire-rated wall**
- D. Use dilution ventilation to control fire hazards created by leaking cylinders